HASSAN DIVISION.

Dated 30th April 1928.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 2 P.M. on 28th May 1928, for constructing a Gosha Ward for the Maternity Hospital and for adding a room with a connecting corridor to the Local Fund Dispensary at Saklespur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M. on all working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 150 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Gosha Ward for the Maternity Hospital and for adding room with a connecting corridor to the Local Fund Dispensary at Saklespur in default of which tenders will be rejected."

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond : in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract Estimate for constructing a Gosha Ward for the Maternity Hospital at Saklespur.

Serial No.	Items of work	Per	Quantity
1	Earthwork excavation and filling in basement ...	C.yd.	49
2	Concrete in chunnam	C.ft.	533
3	Burnt size stone in mortar	,,	1,053
4	Burnt brick in mud	,,	1,260
5	Do in mortar	,,	383
6	Burnt stone slabs 6" thick and dressed	S.ft.	247
7	Teakwood panneld doors with hinges, complete ...	,,	119
8	Teakwood window with iron bars of ½" with pannel and glazed shutters, complete.	,,	124
9	Teakwood wrought and put up and oiling, complete ...	C.ft.	68·90
10	Roofing with first class Mangalore tiles over teak reepers	Sqr.	12·96
11	Ridge tiles set in mortar	R.ft.	94
12	Teakwood square pillars, 6" × 6" with base and capitals ...	Each	12
13	Chunnam plastering	Sqr.	25·60
14	Cement pointing	,,	1·85
15	Teakwood ornamental eave board	R.ft.	132
16	White and colour washing	Sqr.	27·45
17	Flooring with Mangalore tiles over 3" concrete and cement pointing.	,,	3·70
18	Flooring with Cuddapah slabs over 3" concrete and cement pointing.	,,	3·21
19	Chocolate painting	,,	7·46
20	Teakwood finials	Each	2

Abstract estimate for adding a room with a connecting corridoor to the Local Fund Dispensary at Saklespur.

Serial No.	Items of work	Per	Quantity
1	Earthwork excavation and filling foundation and basement.	C.yd.	26
2	Chunam jelly concrete	C.ft.	203
3	Size stone in mortar	,,	586
4	Burnt brick in mud	,,	749
5	Chunam plastering	Sqr.	14·65
6	Burnt stone slabs 6" thick dressed	S.ft.	104
7	Burnt brick in mortar	C.ft.	229
8	Teakwood pannelled door, complete	S.ft.	56
9	Do windows with glazed and pannel shutters, complete with iron bar and fitting.	,,	41
10	Dismantling wall and removing the existing window from the room and fixing a new door and rebuilding the sides of the same with brick in mortar and plastering, complete.	Each	1
11	Teakwood wrought and to put up with wood oiling, complete.	C.ft.	34·40
12	Roofing with 1st Class Mangalore tiles on teak reepers, complete.	Sqr.	5·30
13	Ridge tiles set in mortar	R.ft.	30
14	Flooring with Cuddapah slabs over 3" concrete and cement pointing, complete.	Sqr.	0·62
15	Flooring with 1st Class Mangalore tiles over 3" concrete and cement pointing.	,,	1·43
16	White and colour washing	,,	15·88
17	Chocolate painting two coats	,,	3·94
18	Teakwood ornamental eave board	R.ft.	98
19	Cement pointing to basement	Sqr.	1·23
20	Teakwood glazed ventilator, complete	S.ft.	21
21	Clearing site levelling ground	Lump	sum

R. L. STEELE,
Executive Engineer.

GOVERNMENT OF MYSORE, ELECTRICAL DEPARTMENT.

Dated 3rd May 1928.

Notice is hereby given that sealed tenders will be received at the Office of the General Superintendent, Generating Station, Sivasamudram, up to 2 P.M., on 25th May 1928, for constructing one Block of Line Inspector's Quarters with Out-Houses, Latrine and Stables at Ramapuram along the Metur Transmission Line. The tenders will be opened in public at 2 P.M., on Friday the 25th May 1928. The time required to complete the work and monthly progress should be indicated as these will be some of the chief factories in the award of tenders.

2. The plans, detailed estimate and conditions may be obtained at the Chief Electrical Engineer's Office, Bangalore, and also at the General Superintendent's Office, Sivasamudram, between the hours of 11 A.M. and 5P.M. on all working days.

3. Tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 75 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing one Block of Line Inspector's Quarters with Out-Houses, Latrine and Stables at Ramapuram along the Metur Transmission Line," in default of which, tenders will be rejected. 6 c